

BRUHAT BANGALORE MAHANAGARA PALIKE


BBMP/2014-15/OW/WORK_IDENT14613

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/07/2014-15, Date: 31.10.2014

Improvements to Roads in Behind Ayyapa swamy temple Jakkur layout ward no. 07 Byatarayanapura .

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				Gnanendra Reddy	
				In Figures	In Words
1	48.30	KSRRB 300-1. Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. No. 138 Item No. 19.2/ PWD SR 2014-15.	Cum	104.78	Rupees One Hundred Four and Seventy Eight Paise Only
2	48.30	KSRRB 300-3. Earthwork excavation and foming in embankment by manual means in ordinary soil with initial lead upto 15 m. and lift of 1.5m. (When earth is taken from bank cutting or from borrow pits) including breaking of clods, spreading to required line and level, forming, and cost of all labour complete as per specifications. (excluding watering and compaction of earth) (P 138, I.No. 19.3) SR-2014-15	Cum	96.23	Rupees Ninety Six and Twenty Three Paise Only
3	69.00	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. (P. 145, I.No. 19.64) SR-2014-15	Sqm	4.44	Rupees Four and Forty Four Paise Only
4	69.00	KSRRB 300-64.2. Extra for watering the earth to bring the earth upto required optimum moisture content with mechnery including cost of all labour, HOM of machineries complete as per specifications. (P. 146, I.No. 19.72) SR-2014-15	Cum	2.14	Rupees Two and Fourteen Paise Only
5	72.45	KSRB 4.2.1 : Providing and laying in position reinforced cement concrete of nominal mix 1:1:2 with 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.(excluding cost of steel, fabrication & plastering) (p/ 13, I.No. 4.10) SR-2014-15	Cum	6220.61	Rupees Six Thousand Two Hundred Twenty and Sixty One Paise Only
6	48.30	Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges) Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-341 Kg/cum) (P. 18, I.No. 4.49.1) SR-2014-15	Cum	5788.65	Rupees Five Thousand Seven Hundred Eighty Eight and Sixty Five Paise Only
7	69.00	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift. (P. 171 I. No. 22.7) SR-2014-15	Sqm	96.23	Rupees Ninety Six and Twenty Three Paise Only


G.N. (S.P.)

8	67.50	Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. for concrete pavement(P. 172 I. No. 22.8.1) SR-2014-15	Rmtr	122.96	Rupees One Hundred Twenty Two and Ninety Six Paise Only
9	16.20	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 (P. 5, I.No. 2.3) SR-2014-15	Cum	174.28	Rupees One Hundred Seventy Four and Twenty Eight Paise Only
10	16.20	KSRB 4-1.2: Providing and laying in position plain cement concrete of I mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P. 12, I.No. 4.2) SR-2014-15	Cum	5013.48	Rupees Five Thousand Thirteen and Forty Eight Paise Only
11	7.20	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 (P. 23, I.No. 5.6) SR-2011-12	Cum	3797.8	Rupees Three Thousand Seven Hundred Ninety Seven and Eighty Paise Only
12	9.59	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifcations. Specification No. KBS 4.6.2 (P 15, I.No 4.28) SR-2014-15	Sqm	234.15	Rupees Two Hundred Thirty Four and Fifteen Paise Only
13	4.14	KProviding and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges)Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-3320Kg/cum) (P. 18, I.No. 4.49.1) SR-2014-15	Cum	5788.65	Rupees Five Thousand Seven Hundred Eighty Eight and Sixty Five Paise Only
14	0.20	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (P. 19, I.No. 4.46) SR-2014-15	Ton	77568.32	Rupees Seventy Seven Thousand Five Hundred Sixty Eight and Thirty Two Paise Only

[Signature]
 10.0. (10.0)

15	6.00	KSRB 15.1.3 – do – Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P.109.I.No. 15.3) SR-2014-15	Sqm	90.88	Rupees Ninety and Eighty Eight Paise Only
16	869.88	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means including loading and unloading. From 0.00 to 5.00 Km (Page No.141)	Cum	80.19	Rupees Eighty and Nineteen Paise Only

G. P. Adh

Signature of the Contractor

DE. B. R. S.

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92